



# GTI step forward on sCO<sub>2</sub> Power

Supercritical Transformational Electric Power project

---

G. Subbaraman, M. Lesemann, S. Macadam and M. Kutin  
Gas Technology Institute

IGTC18  
Brussels, Belgium  
October 10, 2018

Contact:  
Markus Lesemann  
Director, Business Development  
markus.lesemann@gastechnology.org  
+1 (919) 599-4096

# Working With Industry and Governments to Increase Access to Abundant, Affordable, and Acceptable Energy

FOR A BETTER ENVIRONMENT AND A BETTER ECONOMY




  
RESEARCH &  
DEVELOPMENT

  
PROGRAM  
MANAGEMENT

  
TECHNICAL/  
ANALYTICAL

  
CONSULTING

  
TRAINING



  
360+  
EMPLOYEES



World-class piloting  
facilities headquartered  
in Chicago area

# Benefits of sCO<sub>2</sub> Power Cycles

## Supercritical CO<sub>2</sub> working fluid advantages:

- Heat source flexibility
- Higher efficiencies
- Compact turbo-machinery
- Economic scalability
- Lower emissions & water consumption
- Facilitates and economizes low-carbon power production

## Versatile Technology – Broad Applicability:



Concentrated Solar



Fossil Fuel



Geothermal




Nuclear



Ship-board Propulsion




Waste Heat Recovery



# Challenges of Advanced sCO<sub>2</sub> Power Cycles

- Technology and process development to confirm advantages
  - Materials: corrosion, creep, fatigue
  - Turbomachinery: life, aero performance, seals
  - Recuperators: design, size, fabrication, durability
  - Power plant operability: startup, transients, load following



Source: NETL

# Supercritical Transformational Electric Power (STEP) Program



**Scope:** Design, construct, commission, and operate a 10 MWe sCO<sub>2</sub> Pilot Plant Test Facility

**Goal:** Advance state of the art for high temperature sCO<sub>2</sub> power cycle performance from Proof of Concept (TRL3) to System Prototype validated in an operational system (TRL7)

**Team:** Gas Technology Institute (GTI)  
Southwest Research Institute® (SwRI®)  
General Electric Global Research (GE-GR)  
U.S. Department of Energy (NETL)

**Schedule:** Three budget phases over six years (2016-2022)

**Cost:** \$119MM Total / \$84MM Federal Funding

**Building a flexible platform for long-term use to validate component performance, quantify cycle efficiency, and study plant operability in an integrated, grid-connected system.**



# STEP Program Objectives


Demonstrate pathway to RCBC cycle efficiency  $> 50\%$

Demonstrate cycle operability up to  $700^{\circ}\text{C}$  turbine inlet temperature and 10 MWe net power generation

Quantify performance benefits:

- 2-5% point net plant efficiency improvement
- 3-4% reduction in LCOE
- Reduced emissions, fuel, and water usage


Reconfigurable facility to accommodate future testing



Pilot Site: SwRI in San Antonio, TX






# STEP Project Plan




# Transitioning from Component and Cycle Design to Integrated System Demonstration


## Individual Cycle and Component Development Efforts



## Integrated Pilot Scale System Demonstration




# Flexible Test Facility Designed with Alternate Indirect Cycle Configurations



## Simple Cycle

- Shortest time to initial data
- Controls & safety
- Component performance
- Steady & transient cycle data



## Recompression Cycle

- Inventory management
- Starting transients
- Parallel compressor control
- SOA component efficiencies
- Cycle efficiency > 50%

# STEP Program Achievement Status


- › Ground Breaking – October 15<sup>th</sup>, 2018
- › Purchase orders issued for major hardware
  - › Process Heater, Compressor, HTR, Cooling Tower
- › Facility bid package release in November
- › Turbine design complete in December
- › Joint Industry Program (JIP) – established




Seal development testing  
nearing completion



Process heater and building



Turbine




Arrangement inside building

# STEP Current Status: Turbine


## ➤ Turbine improvements over SunShot

- Increased casing and rotor life, 100,000 hrs vs 20,000 hrs
- Increase bolt retightening schedule to 30,000 hr vs 1,000 hrs
- Design for couplings on both shaft ends
- Improved aero performance with increased volute flow area





## ➤ Current activities

- Design to be completed in December
- Long lead material being ordered




# STEP Current Status: Recuperators


- Heatric under contract for HTR vendor
- Evaluating suppliers for other units (3)
- Alternate compact technologies
  - heat transfer surface vs. volume
- STEP is a significant scale-up
- Evaluating performance vs. cost and plant integration




# STEP Current Status: Other Major Components



**Compressor  
BHGE**



**Cooling Tower  
TAS**





**Process Heater  
Optimus**




# STEP Current Status: Facility and Site

- › Facility design in review
- › Bid package to be issued in November
- › Ground breaking next week
- › Construction scheduled to start in spring 2019



# sCO<sub>2</sub> Step-by-Step Commercialization



*Early product off-ramp for 10-20 MWe distributed power generation systems*

# Joint Industry Program (JIP)

Leverage \$84 MM in US DOE funding and \$35+ MM in industry funding to determine how this technology fits into your plans and influence project direction

## 1. Steering Committee Level - \$250k/year for 6 years (or equivalent)

- Input and advisory recommendations to the project team
- Direct participation in bi-monthly advisory meetings, attendance at bi-annual technical interchange meetings
- Receipt of quarterly technical status reports
- Real time access and use of Project System Data
- Opportunity for facility visits and training in system operations
- Period of exclusive access to license system IP

## 2. Associate Membership - \$100k/year for 6 years (or equivalent)

- Attendance at bi-annual technical interchange meetings
- Receipt of quarterly technical status reports
- Opportunity for 2 site visits per year

# Summary

- sCO<sub>2</sub> power cycles promise substantial cost and emissions benefits
- Applicable to coal, natural gas, solar, geothermal, nuclear, waste heat
- STEP Demo will demonstrate 10MW<sub>e</sub> grid-connected sCO<sub>2</sub> power plant
  - Reconfigurable facility to accommodate future testing
- Groundbreaking at SwRI in October 2018
- Joint Industry Program allows for international industry participation
  - Additional partners welcome



# Acknowledgment and Disclaimer

---

Acknowledgment: "This material is based upon work supported by the Department of Energy under Award Numbers DE-FE0028979."

Disclaimer: "This report was prepared as an account of work sponsored by an agency of the United States Government. Neither the United States Government nor any agency thereof, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, apparatus, product, or process disclosed, or represents that its use would not infringe privately owned rights. Reference herein to any specific commercial product, process, or service by trade name, trademark, manufacturer, or otherwise does not necessarily constitute or imply its endorsement, recommendation, or favoring by the United States Government or any agency thereof. The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof."

# Contact

---

[www.stepdemo.us](http://www.stepdemo.us)

Markus Lesemann



Director, Business Development, GTI

[Markus.Lesemann@gastechnology.org](mailto:Markus.Lesemann@gastechnology.org)

+1 (919) 599 4096

[www.gastechnology.org](http://www.gastechnology.org)

# Turning Raw Technology into Practical Solutions



[www.gastechnology.org](http://www.gastechnology.org) | [Ganesan.subbaraman@gastechnology.org](mailto:Ganesan.subbaraman@gastechnology.org)